





-  440 x 215 x 100 Roadstone Standard Blocks
-  440 x 215 x 100 Roadstone Thermal Liteblock



Roof build-up:
Varies, to achieve Roof U values within the 0.21 or 0.15 Wall type Ranges (refer to Appendix D of TGD part L 2011)



Wall build-up:
Varies, to achieve U values within the 0.21 or 0.15 Range (refer to Appendix D of TGD part L 2011)

The diagrams, drawings and details included in this brochure are for indicative purposes only. They do not constitute nor should they be relied upon as giving/providing any design detail. They focus on the issues of thermal performance only. Insulation thicknesses of the main building elements have not been provided, as these are dependent on the thermal properties of the materials chosen, as well as on the desired U value. These diagrams, drawings and details illustrate good practice for the design and construction of interfaces solely in connection with thermal performance. The product should be used with due regard to all other requirements imposed by the Building Regulations and advice should be sought from a design professional in connection with the use of this product where required.



Roadstone Custom Psi values		
U Value Range (W/m²K)	Part L (Ψ)	Roadstone TLB Psi (Ψ) Value
0.21	0.040	0.039

As modelled by NSAI registered Thermal Modellers:

 NSAI Agreement	 NSAI Agreement
Diarmuid Hynes Evulsion Innovation ltd. Registration Number IAB/TM/04 NSAI Approved Thermal Modeller	Andrew Dunne Evulsion Innovation ltd. Registration Number IAB/TM/07 NSAI Approved Thermal Modeller

All options pass FRsi assessment, no surface condensation predicted

*Note:

In the 0.21 U Value Range the model surpasses the default Psi value and therefore a y-value of 0.08 can be assumed using this option without a y-value calculation, provided all other details in the building comply with the published ACDS and/or Roadstone modelled details.

REVISION: **A**

DWG. NO.: **DETAIL RS 1.19**

DATE: **September 2018**

SCALE: **NTS**

JUNCTION: **PARTIAL FILL CAVITY WALL/ FLAT ROOF - EAVES**

TO BE READ IN CONJUNCTION WITH Y-VALUE CALCULATION

